

TRADE AND ENVIRONMENTAL SUSTAINABILITY STRUCTURED DISCUSSIONS (TESSD)

COMMUNICATION FROM THE UNITED KINGDOM

Addendum¹

The following communication, dated 23 May 2023, is being circulated at the request of the delegation of the United Kingdom.

OFFSHORE WIND ENERGY

Technical paper by the United Kingdom

ANNEX I.

VALUE CHAIN DIAGRAMS FOR OFFSHORE WIND ENERGY

Value chain diagrams – key:

Chevron Colour	Meaning
	Activity or process involved in the ' Development and project management ' stage of an offshore wind farm's lifecycle. In the delivery of a service, this represents a sub-stage of service delivery. In the delivery of a good (whether it is an input, intermediate, or final good), this represents a manufacturing activity or production process.
	Manufacturing activity or production process involved in either the manufacture or assembly of a wind turbine
	Manufacturing activity or production process involved in the manufacture, assembly, or installation of an offshore wind farm's balance of plant equipment
	Manufacturing activity, production process, or installation process involved in the final installation and commissioning of an offshore wind farm
	Manufacturing activity, production process, or installation process involved in the ' Operation, maintenance and service ' stage of an offshore wind farm
	Activity or process involved in the 'Decommissioning' stage of an offshore wind farm's lifecycle
	Input product, intermediate product, final product, or a service deliverable in any stage of an offshore wind farm's lifecycle

¹ This Addendum supplements the paper titled "Offshore Wind Energy – Submission of Information to trade and Environmental Sustainability Structured Discussions (TESSD) from the United Kingdom", [INF/TE/SSD/W/26](https://www.wto.org/Trade_Environment/TE/SSD/W/26/).


Contents

I.1. DEVELOPMENT AND PROJECT MANAGEMENT	3
I.1.1. Development and consenting services.....	3
I.1.2. Environmental surveys.....	4
I.1.3. Resource and metocean assessment.....	6
I.1.4. Geological and hydrographical surveys.....	8
I.1.5. Engineering consultancy.....	9
I.2. Wind Turbine.....	10
I.2.1. Nacelle.....	10
I.2.2. Rotor.....	12
I.2.3. Tower.....	14
I.3. Balance of plant.....	16
I.3.1. Cables.....	16
I.3.2. Turbine foundation.....	17
I.3.3. Offshore substation.....	18
I.3.4. Onshore substation.....	19
I.3.5. Operations base.....	20
I.4. Installation and commissioning.....	21
I.4.1. Foundation installation.....	21
I.4.2. Offshore substation installation.....	23
I.4.3. Onshore substation construction.....	24
I.4.4. Onshore export cable installation.....	25
I.4.5. Offshore cable installation.....	26
I.4.6. Turbine installation.....	27
I.4.6.1. Commissioning.....	28
I.4.7. Construction port.....	29
I.4.8. Offshore logistics.....	30
I.5. Operation, maintenance and service.....	31
I.5.1. Operations.....	31
I.5.1.1. Training.....	31
I.5.2. Maintenance and service.....	35
I.5.3. Balance of plant maintenance and service.....	36
I.6. Decommissioning.....	37
I.6.1. Turbine decommissioning.....	37
I.6.2. Foundation decommissioning.....	38
I.6.3. Cable decommissioning.....	39
I.6.4. Substation decommissioning.....	40
I.6.5. Decommissioning port.....	41
I.6.6. Reuse, recycling or disposal.....	42

I.1. Development and project management

I.1.1. Development and consenting services


Development and consenting covers the work needed to secure consent and manage the development process through to financial close.



I.1.2. Environmental surveys

To determine the environmental impacts, a full suite of environmental surveys of the wind farm location and its surroundings is undertaken. These surveys establish the baseline for the assessment and allow impact modelling to be undertaken.

- **Benthic environmental surveys:** Benthic studies survey species that live on the sea bed and in sediment. The survey data and analysis is used to define areas of similar environmental conditions on the sea bed and to inform habitat and species impact studies.
- **Fish and shellfish surveys:** establish what species are present in the water column within the proposed wind farm site and surrounding areas. The resulting data is used to inform impact analysis and reporting.
- **Ornithological surveys:** establish the presence and behaviour of birds within the wind farm boundary and surrounding areas. The data from these bird surveys is used to establish the risks to birds that a wind farm may pose.
- **Marine mammal surveys:** establish the diversity, abundance, distribution and behaviour of cetaceans (including porpoises, dolphins and whales) and seals within the wind farm boundary and surrounding areas. Surveys are typically undertaken monthly for at least two years to establish how these variables change across seasons and between years. The data from these surveys is used to establish the potential impacts to marine mammals that a wind farm may pose.
- **Onshore environmental surveys:** consider the potential ecological impact that cable-laying and onshore substations may have on the onshore environment.
- **Human impact studies:** assess the impact that a proposed wind farm may have on the community living in and around the coastal area near the wind farm.




Many of above services likely
CPC (2.1) 83931 –
 (Environmental consulting
 services)

I.1.3. Resource and metocean assessment


A resource and metocean assessment is carried out to provide atmospheric and oceanographic datasets to inform the engineering design of a wind farm, the potential future energy production, and to fully describe the likely operating conditions at the proposed wind farm location.

- **The structure:** provides the mounting for the meteorological and metocean, sensors and auxiliary systems plus safe access for personnel.
- **Sensors:** provide data on meteorological and oceanographic conditions at the site of interest. Data loggers provide data storage, processing and remote communications capability.
- **Maintenance:** Offshore wind and metocean systems will require maintenance, including inspection, cleaning and refuelling (where diesel generators or hydrogen fuel cells or similar are used).



I.1.4. Geological and hydrographical surveys

Seabed surveys analyse the sub seabed environment of the proposed wind farm site and export cable route to assess its geological condition and engineering characteristics. The data collected is utilised in a wide range of engineering and environmental studies through the design and development phase.



I.1.5. Engineering consultancy

Front-end engineering and design (FEED) studies address areas of wind farm system design and develop the concept of the wind farm in advance of procurement, contracting and construction. Earlier on in the process, pre-FEED studies are used to develop an outline concept of the project for the purposes for defining the consent envelope and to inform environmental impact studies. The FEED study is continually refined through the development process and is ultimately used to frame and process substantial engineering and procurement decisions.



I.2. Wind Turbine

The turbine converts kinetic energy from the wind into three-phase AC electrical energy.

I.2.1. Nacelle


The nacelle supports the Rotor and converts the rotational energy from the rotor into three-phase AC electrical energy.

- **Bedplate:** supports the drive train and the rest of the nacelle components and transfers loads from the rotor to the tower.
- **Main bearing:** supports the rotor and transfers some of the rotor loading to the nacelle Bedplate.
- **Main shaft:** transfers torque from the rotor to the gearbox or, for some direct drive designs, the generator. It is supported at the rotor end by the main shaft bearing and at the other end either by the gearbox / generator or separately mounted bearing.
- **Gearbox:** converts rotor torque at a speed of 5-15 rpm to a speed of up to about 600 rpm for a medium speed gearbox and 1500 rpm for a high-speed gearbox for conversion to electrical energy by the generator.
- **Generator:** converts mechanical energy to electrical energy.
- **Power take-off:** receives electrical energy from the generator and adjusts voltage and frequency for onward transfer to the wind farm distribution system.
- **Control system:** provides supervisory control (including health monitoring) and active power and load control in order to optimise wind turbine life and revenue generation, while meeting externally imposed requirements.
- **Yaw system:** orients the nacelle to the wind direction during operation.
- **Yaw bearing:** connects the nacelle and tower, enabling the yaw system to orient the nacelle to any wind direction during operation.
- **Auxiliary systems:** facilitate ongoing unattended operation of the wind turbine for the vast majority of the time, and support planned maintenance, which typically should be only on an annual basis.
- **Nacelle cover:** provides weatherproof protection to the nacelle components plus support and access to external components such as coolers, wind measurement equipment and lighting protection devices.
- **Small engineering components:** make up the rest of the nacelle assembly.
- **Structural fasteners (either bolts or studs):** are used in a range of critical bolted joints, for example connecting rotor to main shaft, main bearing housings to nacelle bedplate and yaw bearing to the underside of nacelle bedplate.
- **Condition monitoring systems:** provide additional health checking and failure prediction capability.

I.2.2. Rotor

The rotor extracts kinetic energy from the air and converts this into rotational energy in the drive train.


- **Blades:** capture the energy in the wind and transfer torque and other unwanted loads to the drive train and rest of the turbine.
- **Hub:** connects the blades to the main shaft.
- **Blade bearings:** enable adjustment of blade pitch angle to control power output from the turbine, minimise loads and start/stop turbine as required.
- **Pitch system:** adjusts the pitch angle of the blades to control power output from the turbine, minimise loads and start/stop turbine as required.
- **Spinner:** provides environmental protection to the hub assembly and access into the hub and blades for maintenance personnel.
- **Rotor auxiliary systems:** may be incorporated to lubricate bearings and provide condition monitoring and advanced control inputs.
- **Fabricated steel components:** often required to stiffen the blade bearing support and provide a connection for hydraulic pitch system actuators.



I.2.3. Tower

The tower is typically a tubular steel structure that supports the nacelle. It also provides access to the nacelle and houses electrical and control equipment. Also provides shelter and storage for safety equipment.

- **Steel:** the most commonly used material for the manufacture of towers.
- **Tower internals:** provide means of access, lighting and safety for maintenance and service personnel, plus means of transferring hand tools and components to the nacelle. They provide support for control and electrical cables and housing of switch-gear, transformers and other elements of power take-off. Tower internals also provide storage for survival equipment. A tuned damper may be located at the top of the tower to aide damping of tower and structure resonances.




I.3. Balance of plant

The balance of plant includes all the components of the wind farm except the turbines, including transmission assets built as a direct result of the wind farm.


I.3.1. Cables

The cables deliver the power output from the wind turbines to the grid.




I.3.2. Turbine foundation

The foundation provides support for the wind turbine, transferring the loads from the turbine at the tower interface level (typically around 20m above water level) to the sea bed where the loads are reacted. The foundation also provides the conduit for the electrical cables, as well as access for personnel from vessels.




I.3.3. Offshore substation

Offshore substations are used to reduce electrical losses before export of power to shore. This is done by increasing the voltage, and in some cases converting from alternating current (AC) to direct current (DC). The substation also contains equipment to manage the reactive power consumption of the electrical system including the capacitive effects of the export cables.




I.3.4. Onshore substation

The onshore substation transforms power to grid voltage, for example 400kV. Where a high voltage DC export cable is used, the substation will convert the power three phase AC.



I.3.5. Operations base

The operations base supports the operation, maintenance and service of the wind farm.





I.4. Installation and commissioning

All installation and commissioning of balance of plant and turbines, including land- and sea-based activity. For offshore activities, the process starts by transporting components from the nearest port to manufacture to either the I.7 Construction port or straight to site. Activities are complete at the wind farm construction works completion date, where assets are handed over to operational teams.

I.4.1. Foundation installation


Foundation installation consists of the transport and fixing of foundation in position.






I.4.2. Offshore substation installation

The installation of the offshore substation consists of the transfer of the substation from its quayside fabrication site and the installation on the foundation.




I.4.3. Onshore substation construction

The construction of the onshore substation consists of the construction of the infrastructure and the installation of electrical equipment.




I.4.4. Onshore export cable installation

The installation of the onshore export cable completes the connection between the offshore export cable and the onshore substation.




I.4.5. Offshore cable installation

The installation of array cables enables the connection of the wind turbines to the offshore substation whilst the installation of the export cable enables the connection between the offshore and onshore substations.



I.4.6. Turbine installation

Turbine installation involves transportation of the turbine components from the Construction port and installation of the turbine components onto the foundation.




I.4.6.1. Commissioning

After installation, commissioning is the process of safely completing mechanical and electrical assembly, putting all systems to work and addressing punch lists before handover.




I.4.7. Construction port

The construction port is the base for pre-assembly and construction of the wind farm. Separate locations may be used for feeding foundations and the wind turbines to a wind farm. Location is critical as it affects the time spent in shipment and sensitivity to weather windows.



I.4.8. Offshore logistics

Offshore logistics involves coordination and support of offshore installation and commissioning activities.



I.5. Operation, maintenance and service

Operation, maintenance and service (OMS) are the combined functions which, during the lifetime of the wind farm, support the ongoing operation of the wind turbines, balance of plant and associated transmission assets. OMS activities formally start at the wind farm construction works completion date.

The focus of these activities during the operational phase is to ensure safe operations, to maintain the physical integrity of the wind farm assets and to optimise electricity generation.

I.5.1. Operations

Operations relate to management of the asset such as health and safety, control and operation of the asset including wind turbines and balance of plant, remote site monitoring, environmental monitoring, electricity sales, administration, marine operations supervision, operation of vessels and quayside infrastructure, and back office tasks.

I.5.1.1. Training

Training ensures that OMS personnel are qualified to fulfil the roles needed by the wind farm while ensuring their own safety and those of colleagues.




I.5.1.2. Onshore logistics

Onshore logistics involves support and resources to the wind farm operations, including quayside infrastructure, warehousing, logistics and operational planning.




I.5.1.3. Offshore logistics

Offshore logistics involves management and coordination of all marine based activities and operations.




I.5.1.4. Health and safety inspections

Health and safety inspections are a crucial activity to ensure the ongoing safe operation of wind farm infrastructure and systems, and to fulfil statutory obligations to inspect safety critical systems on a regular basis.




I.5.2. Maintenance and service

Maintenance and service activities ensure the ongoing operational integrity of the wind turbines and associated balance of plant, including planned maintenance and unplanned service in response to faults, either proactive or reactive.



I.5.3. Balance of plant maintenance and service

Balance of plant maintenance and service is focused on ensuring the operational integrity and reliability of all wind farm assets other than the wind turbines, including the substation(s), foundations, array cables, export cables, scour protection and corrosion protection systems.




I.6. Decommissioning

Removal or making safe of offshore infrastructure at the end of its useful life, plus disposal of equipment.


I.6.1. Turbine decommissioning

Complete removal and shipment to shore of turbine rotor, nacelle and tower.




I.6.2. Foundation decommissioning

Removal and shipment to shore or cut-off at sea bed level and making safe.




I.6.3. Cable decommissioning

Removal and shipment to shore.




I.6.4. Substation decommissioning

Decommissioning plans typically are required as part of gaining approval to construct. These may define specific requirements for removal of components below the mud line which in turn may drive the choice or design of substation foundations and installation methods.



I.6.5. Decommissioning port

Port where equipment removed is offloaded and marshalled for next stage of processing.



I.6.6. Reuse, recycling or disposal

Once equipment is onshore, there is a motivation to extract maximum value via reuse, recycling or disposal.

